


The following items and quantities are included in the scope of works:

Project/ Number	Description	Quantity/ Unit	Unit Cost (Php)	Total Amount (Php)	
IB No. CW- 2020-101	A	BUILDING			
	B.5	Project Billboard/Sign Board	2.00 ea	7,041.28	14,082.56
	B.7	Occupational Safety & Health	9.00 months	32,992.99	296,936.91
	A 1.1(8)	Construction of Temporary Facility	1.00 unit	402,483.86	402,483.86
	1000(1)	Soil Poisoning	1,140.00 m ²	247.11	281,705.40
	803(1)a	Lay/Stake out and Excavation	1,043.12 m ²	333.79	348,183.02
	804(1)a	Embankment from Structure Excavation	297.70 cu.m	192.65	57,351.91
	804(1)b	Embankment (from Common Borrow)	911.90 m ³	787.90	718,486.01
	902(1)a1	Reinforcing Steel, Grade 40	185,206.65 kg	66.71	12,355,135.62
	903(2)	Formworks and Falseworks (for one storey building)	1.00 L.S	1,644,752.88	1,644,752.88
	900(1)	Lean Concrete (for manual mixing)	37.92 m ³	4,816.23	182,631.44
	900(1)c2	Structural Concrete for Footing and Slab on Fill (Class A, 28 days)	444.66 m ³	6,158.32	2,738,358.57
	900(1)c3	Structural Concrete for Footing Tie Beam, Column, Suspended Slab, Girder/ Beam (Class A, 28 days)	539.54 m ³	6,770.97	3,653,209.15
	1046(2)a1	100mm CHB Non-Load Bearing (incl. Reinforcing Steel)	716.42 m ²	713.66	511,280.30
	1046(2)b	150mm CHB Non-Load Bearing (including Reinforcing Steel)	477.76 m ²	934.15	446,299.80
	1027(1)	Cement Plaster Finish	2,183.55 m ²	162.23	354,237.32
	1047(1)	Structural Steel Roof Framing	3,092.21 kg	111.61	345,121.56
	1014(1)b1	Pre-painted Metal Sheets (inc. Spandrel Ceiling)	481.64 m ²	2,107.62	1,015,114.10
	1013(2)	Fabricated Metal Roofing Accessories	4.80 ln.m	6,046.74	29,024.35
	1003	Carpentry and Joinery Works	768.00 m ²	1,454.65	1,117,171.20
	1010	Doors	40.74 m ²	6,315.34	257,286.95
	1008	Aluminum Glass Window	154.09 m ²	4,447.48	685,312.19
	1100-1103	Electrical Works	1.00 l.s	1,401,774.32	1,401,774.32
	1002	Plumbing	1.00 l.s	581,874.39	581,874.39
	1001(11)	Septic Vault (Concrete/CHB)	1.00 l.s	137,837.86	137,837.86
	1001(6)	Catch Basin (Concrete/CHB)	1.00 l.s	114,861.07	114,861.07
	1018	Ceramic/Granite Tiles	1,289.90 m ²	1,994.31	2,572,460.47
	1032(1)a	Painting Works (Masonry, Concrete)	2,863.95 m ²	274.43	785,953.80
	1032(1)b	Painting Works (Wood)	103.48 m ²	307.45	31,814.93
	1032(1)c	Painting Works (Steel)	185.00 m ²	293.18	54,238.30
	1003(15)b	Moulding (concrete)	1,099.46 m	633.66	696,683.82
	1051(6)	Railing	217.90 ln.m	3,257.40	709,787.46
	1005(6)	Window Accesory	1.00 L.S	36,194.58	36,194.58
B	LAND DEVELOPMENT				
804(1)b	Embankment (from Common Borrow)	431.42 cu.m	797.73	344,156.68	
TOTAL			Php 34,921,802.88		

IN WITNESS whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

Signed sealed, delivered by **HUMERLITO A. DOLOR, MPA, Ph.D.**, the Provincial Governor for the Provincial Government of Oriental Mindoro.

Signed sealed, delivered by **ENGR. ARMIN C. SUZARA**, the Proprietor, for the **811 TRADING & CONSTRUCTION**.

By: **PROCURING ENTITY**

HUMERLITO A. DOLOR, MPA, Ph.D.
 Provincial Governor

By: **CONTRACTOR**

ARMIN C. SUZARA
 Proprietor

WITNESSES:


ENGR. EDYLOU B. TEJIDO
 Provincial Engineer


ALTHEA F. AGUTAYA
 PGDH -Provincial Accountant
 As to Funds Availability