



Republic of the Philippines
PROVINCIAL GOVERNMENT OF ORIENTAL MINDORO
 Camilmil, Calapan City 5200, Oriental Mindoro

BIDS AND AWARDS COMMITTEE

INVITATION TO BID
IB NO. CW 2022 – 132

Construction of School Building at Bugtong na Tuog, Socorro, Or. Mindoro

1. The **Provincial Government of Oriental Mindoro (PGOM)** through the **LGSF-SBDP FY 2021** intends to apply the sum of **Five Million Nine Hundred Ninety Thousand Six Hundred Fifty four Pesos and 98/100 Only (Php 5,990,654.98)** being the approved Budget for the Contract (ABC) to payment under the contract for **“Construction of School Building at Bugtong na Tuog, Socorro, Or. Mindoro”**. Bids received in excess of the ABC shall be automatically rejected at bid opening.

2. The PGOM now invites bids for **“Construction of School Building at Bugtong na Tuog, Socorro, Or. Mindoro”**. Completion of the Works is **238 calendar days**. Bidders should have completed within five (5) years before the date of submission and receipt of bids, a single completed contract similar to the Project worth at least fifty percent (50%) of the ABC. The description of an eligible bidder is contained in the Bidding Documents, particularly, in Section II. Instructions to Bidders.

Item No.	DESCRIPTION	Qty/Unit
PART I	FACILITIES FOR THE ENGINEER	
A.1.1(3)	Construction of Field Office for the Engineer	
PART III	OTHER GENERAL REQUIREMENTS	1.00L.S
B.5	Project Billboard/Sign Board	
B.7(2)	Occupational Safety and Health Program	1.00ea
PART III	CIVIL, MECHANICAL, ELECTRICAL, SANITARY/PLUMBING WORKS	5.20mo
PART A	EARTHWORKS	
800(2)	Clearing and Grubbing	1.00l.s
803(1)a	Structure Excavation (Common Soil, Manual Excavation)	79.41m3
804(1)a	Embankment from Structure Excavation	28.98m3
804(1)b	Embankment from Borrow	118.00m3
804(4)	Gravel Fill	11.26m3
PART B	PLAIN AND REINFORCED CONCRETE WORK	
900(1)c2	Structural Concrete (Footing and Slab on Fill), Class A, 28 days	35.98m3
900(1)c3	Structural Concrete (Footing Tie Beam & Wall Footing), Class A, 28 days	16.16m3
900(1)c4	Structural Concrete (Column), Class A, 28 days	11.67m3
900(1)c5	Structural Concrete (Suspended Slab), Class A, 28 days	5.04m3
900(1)c6	Structural concrete (Beams/Girders), class A, 28 days	27.41m3
902(1)a1	Reinforcing Steel, Grade 40	13,149.62kg
903(2)	Formworks and Falseworks	2,631.00bd.ft
PART C	FINISHING	
	C.1 Termite Control Works	
1000(1)	Soil Poisoning	14.00L
	C.2 Masonry Works	
1046(2)a1	100mm CHB Non-Load Bearing (including Reinforcing Steel)	272.84m2
1046(2)a2	150mm CHB Non-Load Bearing (including Reinforcing Steel)	423.10m2
	C.3 Fabricated Materials	
1003(17)	Carpentry and Joinery Works	1.00l.s
1004(2)	Finishing Hardwares	1.00l.s
1009(1)a	Jalousie Window	1.00l.s
1010(2)a	Hollow Flush Door	15.90m2
1010(2)b	Wooden Panel Door	9.60m2
	C.4 Finishing Works	
1003(1)a1	Fiber Cement Board Ceiling on Metal Frame	250.00m2
1018(1)	Glazed Tiles and Trims	34.98m2
1018(2)	Unglazed Tiles	22.60m2
1021(1)c	Cement Floor Finish with Floor Hardener	171.00m2
1027(1)	Cement Plaster Finish	911.25m2
1038(1)	Reflective Insulation	215.00m2
1051(6)	Railings	1.00l.s