



Republic of the Philippines  
**PROVINCIAL GOVERNMENT OF ORIENTAL MINDORO**  
 Camilmil, Calapan City 5200, Oriental Mindoro

**BIDS AND AWARDS COMMITTEE**

Item No.	DESCRIPTION	Qty/Unit
<b>PART C</b>	<b>FINISHING</b>	
	<b>C.1 Painting Works</b>	
1032(1)a	Painting Works, Concrete	18.00m2
1032(1)c	Painting Works, Steel	93.70m2
	<b>C.2 Structural Steel Works</b>	
1047(1)	Structural Steel	2,137.10kg
1047	Metal Structure Accessories	1.00ls
<b>PART D</b>	<b>ELECTRICAL</b>	
1103(1)	Lighting Fixtures	40.00pcs

**Installation of Solar Streetlights at Sta. Isabel, Naujan, Or. Mindoro**  
**Approved Budget for the Contract: Php 497,853.68**  
**Completion Period: 11 calendar days**

Item No.	DESCRIPTION	Qty/Unit
<b>PART I</b>	<b>OTHER GENERAL REQUIREMENTS</b>	
B.5	Project Billboard/SignBoard	1.00ea
<b>PART II</b>	<b>CIVIL, MECHANICAL, ELECTRICAL, SANITARY/PLUMBING WORKS</b>	
<b>PART A</b>	<b>EARTHWORKS</b>	
803(1)a	Structure Excavation (Common Soil, Manual Excavation)	3.25m3
<b>PART B</b>	<b>PLAIN AND REINFORCED CONCRETE WORK</b>	
900(1)	Structural Concrete, Class A, 28 days	1.94m3
902(1)a1	Reinforcing Steel, Grade 40	234.62kg
903(2)	Formworks and Falseworks	20.28m2
<b>PART C</b>	<b>FINISHING</b>	
	<b>C.1 Painting Works</b>	
1032(1)	Painting Works	36.30m2
	<b>C.2 Structural Steel Works</b>	
1047(1)	Structural Steel	694.56kg
1047	Metal Structure Accessories	1.00ls
<b>PART D</b>	<b>ELECTRICAL</b>	
1103(1)	Lighting Fixtures Formworks and Falseworks	13.00l.s

**Installation of Solar Streetlights at Malaya, Naujan, Or. Mindoro**  
**Approved Budget for the Contract: Php 998,042.84**  
**Completion Period: 20 calendar days**

Item No.	DESCRIPTION	Qty/Unit
<b>PART I</b>	<b>OTHER GENERAL REQUIREMENTS</b>	
B.5	Project Billboard/SignBoard	1.00ea
<b>PART II</b>	<b>CIVIL, MECHANICAL, ELECTRICAL, SANITARY/PLUMBING WORKS</b>	
<b>PART A</b>	<b>EARTHWORKS</b>	
803(1)a	Structure Excavation (Common Soil, Manual Excavation)	6.50m3
<b>PART B</b>	<b>PLAIN AND REINFORCED CONCRETE WORK</b>	
900(1)	Structural Concrete, Class A, 28 days	3.87m3
902(1)a1	Reinforcing Steel, Grade 40	469.25kg
903(2)	Formworks and Falseworks	40.56m2
<b>PART C</b>	<b>FINISHING</b>	
	<b>C.1 Painting Works</b>	
1032(1)a	Painting Works, Concrete	11.70m2
1032(1)c	Painting Works, Steel	60.91m2
	<b>C.2 Structural Steel Works</b>	
1047(1)	Structural Steel	1,389.11kg
1047	Metal Structure Accessories	1.00ls
<b>PART D</b>	<b>ELECTRICAL</b>	
1103(1)	Lighting Fixtures	26.00pcs