



BIDS AND AWARDS COMMITTEE

INVITATION TO BID
IB NO. CW 2023 – 442

Construction of Senior Citizen’s Building Extension at Calocmoy, Socorro, Oriental Mindoro and Construction of Open Canal at Panikihan, Pola, Oriental Mindoro

1. The **Provincial Government of Oriental Mindoro (PGOM)** through the **20% Development Fund 2023** intends to apply the sum of **One Million Four Hundred Ninety Five Thousand Nine Hundred Four Pesos and 27/100 (Php 1,495,904.27)** being the approved Budget for the Contract (ABC) to payment under the contract for **“Construction of Senior Citizen’s Building Extension at Calocmoy, Socorro, Oriental Mindoro and Construction of Open Canal at Panikihan, Pola, Oriental Mindoro”**. Bids received in excess of the ABC shall be automatically rejected at bid opening.

2. The PGOM now invites bids for **“Construction of Senior Citizen’s Building Extension at Calocmoy, Socorro, Oriental Mindoro and Construction of Open Canal at Panikihan, Pola, Oriental Mindoro”**. Completion of the Works is **54 calendar days**. Bidders should have completed within five (5) years before the date of submission and receipt of bids, a single completed contract similar to the Project worth at least fifty percent (50%) of the ABC. The description of an eligible bidder is contained in the Bidding Documents, particularly, in Section II. Instructions to Bidders.

Construction of Senior Citizen’s Building Extension at Calocmoy, Socorro, Oriental Mindoro

ABC: Php 496,743.65

Calendar Days: 30 days

Item No.	DESCRIPTION	Qty/Unit
B.5	Project Billboard/ Sign Board	1.00 ea
803(1)a	Structure Excavation (Common Soil)	11.07 m3
804(1)a	Embankment from Structure Excavation	6.20 m3
804(4)	Gravel Fill	4.47 m3
SPL-1	Chipping of Concrete	1.00 l.s
900(1)	Structural Concrete Class (A) 28 days and Reinforcing Steel, Grade 40	9.38 m3
903(2)	Formworks and Falseworks	89.06 m3
1046(2)a1	100mm CHB Non-Load Bearing (including Reinforcing Steel)	53.44 m2
1009(1)a	Jalousie Window (Glass)	6.72 m2
1010(2)b	Wood Panel Door	2.10 m2
1027(1)	Cement Plaster Finish	106.88 m2
1032(1)a	Painting Works (Masonry Painting)	107.00 m2
1032(1)c	Painting Works, Steel	39.45 m2
1014(1)b1 & 1013 (2)	Pre-painted Metal Sheets & fabricated Metal Roofing Accessories	1.00 l.s
1047(2)a & 1047(2)b	Structural Steel, Trusses & Purlins	428.82 kg
1100	Electrical Works	1.00 l.s

Construction of Open Canal at Panikihan, Pola, Oriental Mindoro

ABC: Php 999,160.62

Calendar Days: 24 days

Item No.	DESCRIPTION	Qty/Unit
B.5	Project Sign Board	2.00 ea.
103(1)a	Structure Excavation	221.90 cu.m
404(1)a	Reinforcing Steel Bars	3,509.35 kg.
405(1)a3	Structural Concrete Class A	33.94 cu.m.
804(4)	Gravel Fill	21.90 cu.m
1027(1)	Cement Plastering	364.00 sq.m.
1046(1)a1	100 mm CHB Non-Load Bearing Wall (including Horizontal Reinforcing Steel)	364.00 sq.m.

3. Bidding will be conducted through open competitive bidding procedures using non-discretionary “pass/fail” criterion as specified in the 2016 Revised Implementing Rules and Regulations (IRR) of Republic Act 9184 (RA 9184), otherwise known as the “Government Procurement Reform Act.”