



Republic of the Philippines  
PROVINCIAL GOVERNMENT OF ORIENTAL MINDORO  
Camilmil, Calapan City 5200, Oriental Mindoro

**BIDS AND AWARDS COMMITTEE**

INVITATION TO BID  
IB NO. CW 2023 – 486

**Construction of SK Building at Alag, Baco, Oriental Mindoro**

1. The **Provincial Government of Oriental Mindoro (PGOM)** through the **General Fund 2023** intends to apply the sum of **Nine Hundred Ninety Nine Thousand Five Hundred Fifty Two Pesos and 50/100 Only (Php 999,552.50)** being the approved Budget for the Contract (ABC) to payment under the contract for **“Construction of SK Building at Alag, Baco, Oriental Mindoro”**. Bids received in excess of the ABC shall be automatically rejected at bid opening.

2. The PGOM now invites bids for **“Construction of SK Building at Alag, Baco, Oriental Mindoro”**. Completion of the Works is **48 calendar days**. Bidders should have completed within five (5) years before the date of submission and receipt of bids, a single completed contract similar to the Project worth at least fifty percent (50%) of the ABC. The description of an eligible bidder is contained in the Bidding Documents, particularly, in Section II. Instructions to Bidders.

Item No.	DESCRIPTION	Qty/Unit
B.5	Project Billboard/Sign Board	1.00ea
800(1)	Clearing and Grubbing	31.20m2
803(1)a	Structure Excation (Common Soil)	20.54m3
804(1)b	Embankment from Borrow	31.20m3
804(4)	Gravel Fill	2.19m3
900(1)c2	Structural Concrete (Footing and Slab on Fill), Class A, 28 days	7.80m3
900(1)c3	Structural Concrete (Footing Tie Beam), Class A, 28 days)	1.44m3
900(1)c4	Structural Concrete (Column), Class A, 28 days	2.12m3
900(1)c6	Structural Concrete (Beams/Girders). Class A, 28 days	2.44m3
902(1)a	Reinforcing Steel, Grade 40	2,036.77kg
903(2)	Formworks and Falseworks	93.49m2
1046(2)a1	100mm CHB Non-Load Bearing (including Reinforcing Steel)	143.15m2
1004(2)	Finishing Hardwares	1.00l.s
1009(1)a	Jalousie Window (Glass)	8.22m2
1010(2)a	Flush Doors	1.68m2
1010(2)b	Wooden Panel Doors	1.89m2
SPL	Aluminum Doors	1.00l.s
SPL-2	Concrete Signage	1.00l.s
1051(6)	Railings	1.00l.s
1003(1)a1	Ceiling, 4.5mm thk. Fiber Cement Board on Metal Frame	34.80m2
1018(5)	Glazed Tiles	36.22m2
1018(2)	Unglazed tiles	2.90m2
1027(1)	Cement Plaster Finish	238.54m2
1032(1)a	Painting Works, Masonry, Concrete & Ceiling	273.34m2
1032(1)b	Painting Works, Wood	3.36m2
1032(1)c	Painting Works, Steel	38.43m2
1032(2)	Varnishing	3.78m2
1013(2)	Fabricated Metal Roofing Accessory	35.20m
1014(1)	Prepainted Metal Sheets, Long Span, above 0.427mm Rib, Type	33.60m2
1047(2)a & 1047(1)b	Structural Steel, Trusses & Purlins	723.51kg
1047(10)	Metal Structure Accessories	1.00l.s
1001(1)	PVC/HDPE Pipes & Fittings	1.00l.s
1002(4)	Plumbing Fixtures	1.00l.s
1001(11)	Septic Vault (Concrete/CHB)	1.00l.s
1100(10)	Conduit Works, Boxes and Fittings	1.00l.s
1101(33)	Wires and Wiring Devices	1.00l.s
1102(1)	Panelboard with Main & Branch Breakers	1.00l.s
1103(1)	Lighting Fixtures and Lamps	1.00l.s