



Republic of the Philippines
PROVINCIAL GOVERNMENT OF ORIENTAL MINDORO
 Provincial Capitol Complex, Calapan 5200, Oriental Mindoro

BIDS AND AWARDS COMMITTEE

NOTICE OF AWARD

February 10, 2022

MR. ALEX D. LAQUI
 Authorized Managing Officer
ADL CONSTRAK
 Bagumbayan, Roxas, Oriental Mindoro

Dear Sir:

Pursuant to **BAC Resolution No. 026, Series of 2022**, we are happy to notify you that the contract for the **Upgrading of Local Access Road, San Isidro, Bulalacao, Oriental Mindoro (Limits: 0+000.00 to 1+191.00; Net Length: 1191.00 meters; Road Width incl. shouldering (m): 8; Road Width (m): 5)** is hereby awarded to your firm as the Bidder with the **Lowest Calculated Responsive Bid** at a contract price equivalent to **SIXTEEN MILLION NINE HUNDRED NINETY ONE THOUSAND SIX HUNDRED SEVEN PESOS AND 23/100 ONLY (Php 16,991,607.23)**.

Project/ Number	Description	Quantity/ Unit	Unit Cost (Php)	Total Amount (Php)
PART A	FACILITIES FOR THE ENGINEER			
A 1.1 (3)	Construction of Field Office for the Engineer	1.00 L.S.	179,572.64	179,572.64
PART B	OTHER GENERAL REQUIREMENTS			
B9	Mobilization and Demobilization	1.00 lot	147,210.00	147,210.00
B.8(1)	Roadway Safety and Traffic Management	105.00 day	2,855.19	299,794.95
B.4.1	Construction Survey and Staking	1.16 km.	11,524.05	13,367.90
B.7(1)	Occupational Safety and Health	3.50 moths	33,195.23	116,183.31
B.5	Project Sign Board	2.00 ea.	5,819.17	11,638.34
PART C	EARTHWORKS			
100(1)	Clearing & Grubbing	11910.00 sq.m	20.50	244,155.00
101(4)a1	Removal of RCPC (24"Ø)- 610mm	16.00 l.m	1,704.30	27,268.80
102(2)a	Roadway Excavation (Surplus Common)	629.74 cu.m	285.99	180,099.34
103(1)a	Structure Excavation	1074.22 cu.m	301.87	324,274.79
104(1)b	Embankment from Roadway Excavation	1757.56 cu.m	289.67	509,112.41
105(1)a	Subgrade Preparation	9528.00 sq.m	22.91	218,286.48
PART D	SUBBASE COURSE			
200(1)	Aggregate Subbase Course	2766.82 cu.m	1,118.34	3,094,245.48
PART E	SURFACE COURSE			
311(1)a1	PCCP- 200 mm thk	5955.00 sq.m	1,212.18	7,218,531.90
PART F	DRAINAGE & SLOPE PROTECTION STRUCTURE			
404	Reinforcing Steel Bars	9238.19 kg	68.94	636,880.82
405	Structural Concrete Class A	43.20 cu.m	7,604.68	328,522.18
500(1)a3	Pipe Culverts, 1200mm dia. (48'Ø)	32.00 l.m	6,570.64	210,260.48
505(5)2a	Grouted Riprap (Class A)	96.97 cu.m	3,854.69	373,789.29
506	Stone Masonry	639.07 cu.m	4,472.77	2,858,413.12
TOTAL				Php 16,991,607.23

The project shall be completed within **One hundred fifty five (155) calendar days**, in accordance with the approved plans, specifications, and program of work.

You are therefore, required within ten (10) days from the receipt of this Notice of Award, to formally enter into a contract with the Provincial Government of Oriental Mindoro.