

The following items and quantities are included in the scope of works:

| Project/ Number | Description | Quantity/ Unit | Unit Cost (Php) | Total Amount (Php) |
|---|--|-------------------|--------------------|--------------------------|
| IB No. CW- 2022- 034 | PART I FACILITIES FOR THE ENGINEER | | | |
| | A.1.1(3) Construction of Field Office for the Engineer | 1.00 L.S | 207,696.28 | 207,696.28 |
| | PART II OTHER GENERAL REQUIREMENTS | | | |
| | B.7(2) Occupational Safety and Health Program | 5.52 mo | 19,386.23 | 107,011.99 |
| | B.5 Project Billboard/Sign Board | 1.00 ea | 9,156.81 | 9,156.81 |
| | PART III CIVIL, MECHANICAL, ELECTRICAL, SANITARY/PLUMBING WORKS | | | |
| | PART A EARTHWORKS | | | |
| | 800(2) Clearing and Grubbing | 1.00 l.s | 9,487.50 | 9,487.50 |
| | 801(1) Removal of Structures and Obstruction | 1.00 l.s | 4,837.50 | 4,837.50 |
| | 803(1)a Structure Excavation (Common Soil, Manual Excavation | 60.20 m3 | 300.21 | 18,072.64 |
| | 804(4) Gravel Fill | 10.00 m3 | 2,227.04 | 22,270.40 |
| | PART B PLAIN AND REINFORCED CONCRETE WORK | | | |
| | 900(1)c2 Structural Concrete for Footing and Slab on Fill (Class A, 28 days) | 25.77 m3 | 9,115.70 | 234,911.59 |
| | 900(1)c3 Structural concrete for Footing Tie Beam (Class A, 28 days) | 4.44 m3 | 10,963.94 | 48,679.89 |
| | 900(1)c4 Structural Concrete for Column & Wall (Class A, 28 days) | 23.55 m3 | 10,105.49 | 237,984.29 |
| | 900(1)c5 Structural Concrete (Suspended Slab), Class A, 28 days | 5.46 m3 | 10,733.49 | 58,604.86 |
| | 900(1)c6 Structural Concrete for beams (Class A, 28 days) | 2.80 m3 | 12,324.71 | 34,509.19 |
| | 902(1)a1 Reinforcing Steel, Grade 40 | 5976.00 kg | 71.15 | 425,192.40 |
| | 903(2) Formworks and Falseworks | 454.67 m2 | 804.82 | 365,927.51 |
| | PART C FINISHING AND OTHER CIVIL WORKS | | | |
| | 1005(5) Steel Window | 1.00 l.s | 19,001.79 | 19,001.79 |
| | 1006(6) Steel Doors and Frames | 1.00 l.s | 13,660.98 | 13,660.98 |
| | 1014(1)b1 Prepainted Metal Sheets, Long Span, above 0.427mm Corrugated Type | 19.68 m2 | 775.63 | 15,264.40 |
| | 1027(1) Cement Plaster Finish | 614.87 m2 | 218.40 | 134,287.61 |
| | 1032(1)c Painting Works, Steel | 132.71 m2 | 222.51 | 29,529.30 |
| | 1046(2)a1 100mm CHB Non-Load Bearing (including Reinforcing Steel) | 62.97 m2 | 891.88 | 56,161.68 |
| | 1047(1)a Structural Steel, Trusses | 113.04 kg | 96.43 | 10,900.45 |
| | 1047(1)b Structural Steel Purlins | 103.87 kg | 119.29 | 12,390.65 |
| | PART D ELECTRICAL | | | |
| | 1100(10) Conduit, Boxes and Fittings (Conduit Works/Conduit Rough-in) | 1.00 l.s | 6,472.80 | 6,472.80 |
| | 1101(33) Wires and Wiring Devices | 1.00 l.s | 52,427.20 | 52,427.20 |
| | 1102(1) PanelBoard with Main & Branch Breakers | 1.00 l.s | 12,982.80 | 12,982.80 |
| | 1102(18) Solar Panel with Inverter, Battery and Other Devices | 1.00 l.s | 359,859.04 | 359,859.04 |
| | 1111(1) Reinforced Concrete Pedestal/Pole | 1.00 l.s | 41,604.63 | 41,604.63 |
| | 1111(5) Manhole | 1.00 l.s | 6,892.54 | 6,892.54 |
| | 1111(8) Spool Insulator Wire Rack | 7.00 set | 419.29 | 2,935.03 |
| PART E MECHANICAL | | | | |
| 1201(2) Centrifugal Pump with control | 1.00 set | 569,594.00 | 569,594.00 | |
| 1201(12) Valves and Pipe Fittings | 1.00 l.s | 189,774.56 | 189,774.56 | |
| DIVISION IV FLOOD CONTROL, DRAINAGE AND WATER SUPPLY | | | | |
| PART I WATER SUPPLY | | | | |
| 1602(5) Polyethelene (HDPE) Plastiv Pipe with Excavation & backfill | 1.00 l.s | 1,292,598.32 | 1,292,598.32 | |
| SPL-I Double Handling | 1.00 l.s | 386,136.00 | 386,136.00 | |
| TOTAL | | | | Php 4,996,816.63 |

IN WITNESS whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

Signed sealed, delivered by **HUMERLITO A. DOLOR, MPA, Ph.D.**, the Provincial Governor for the Provincial Government of Oriental Mindoro.

Signed sealed, delivered by **CLYDE E. SOTTO**, the Authorized Managing Officer, for the **GEMWEALTH CONSTRUCTION AND TRADING CORPORATION**,
PROCURING ENTITY **CONTRACTOR**

By:

HUMERLITO A. DOLOR, MPA, Ph.D.
 Provincial Governor

By:

CLYDE E. SOTTO
 Authorized Managing Officer

WITNESSES:

ENGR. EDYLOU B. TEJIDO
 Provincial Engineer

ALTHEA F. AGUTAYA
 PGDH -Provincial Accountant
 As to Funds Availability